



MEMORANDUM

CITY OF LANGLEY

112 Second St./PO Box 366 Langley, Washington 98260 (360) 221-4246

To: Mayor Samuelson and Members of the City Council
From: Challis Stringer, Director of Public Works *CMS*
Date: September 23, 2010
Re: Funding for Lift Station #2 Pump Upgrade pump(s) quote

One of our goals this year was to complete the Lift Station #2 Upgrade that is laid out in our 2006 Comprehensive Sewer Plan (Sewer Plan). Funds were budgeted in the 2010 Budget from the Sewer Capital Fund in the amount of \$65,000 for the project. We have received a quote for the pumps, which are called for in the Sewer Plan and have been approved by our City Engineer, from APSCO in the amount of \$7,875 for each pump. In addition, we will need stainless steel guide cable assemblies for the pumps and two discharge elbows. Attached is the quote for the equipment needed for the project in the amount of \$17,398.00. We would like to order the equipment while we are waiting for the quotes from the electricians and pipe fitters, as it will take at least 6 weeks for the equipment to arrive.

We recommend you approve the quote from APSCO, for \$17,398.00 for the KSB Submersible pumps, the steel guide cable assemblies and the discharge elbows. We will not be adding the \$1,000.00 as we have verified that we are authorized to complete the form to validate the warranty.

Subject: LS2 Langley Quote Revised
From: "Randi Perry" <Langleyutilities@whidbey.com>
Date: Mon, 20 Sep 2010 12:48:25 -0700
To: "Challis Stringer" <pubwks@langleywa.org>

Please approve so I can get these ordered! This includes the elbows and the guide assembly. Thanks

----- Original Message -----

From: Elaine Stone
To: Randi Perry
Cc: 'Connie Murray'
Sent: Monday, September 20, 2010 8:05 AM
Subject: (Rescued) Langley Quote Revised Request

Dear Randi,

Per your request APSCO is pleased to provide a revised quote as follows:

**Bare Replacement Pump for KSB KRT K 100-316/164XG
Rated for 500 GPM @ 87 ft TDH**

Quantity Two (2) KSB KRT K 100-316/164XG Submersible Pump in Cast Iron Construction with 20 HP 1750 RPM 3/60/460 Volt 1.15 SF Explosion Proof Motor, 50 Foot Power Control Cable, Bi-Metallic Thermal Protection, Motor Stator Moisture Sensor, Guide Claw to mount to existing guide cable system, and KSB Standard Factory Paint. (Impeller to be trimmed to ~ 249mm to meet COS).

Total Net Price for Unit as described above . . . \$ 7,875.00 EACH X Qty 2 = \$ 15,750.00

ADD:

Quantity Two (2) Discharge Elbows and Two (2) KSB Stainless Steel Guide Cable Assemblies for maximum 30 Foot Sump Depth for the above pumps.

Total Net Price Adder \$ 824.00 / Pump X Qty 2 = \$ 1,648.00

Total Revised Price \$ 8,699.00 per pump x Qty 2 = \$ 17,398.00

F.O.B. Richmond, VA. with Freight Prepay and Add to Langley WA.

Estimated Total Shipping Weight 2 Complete Units - 1,300 LBS.

Shipment: 4 – 5 Weeks After Receipt of Order/Release to Manufacture, subject to prior sale.

Randi, for start-up supervision/installation assistance, please Add \$ 1,000.00 / Day portal-to-portal. KSB has a form that needs to be completed by an authorized service tech to fully validate warranty.

The above pricing is based on ordering the elbows and guide cable systems with the pumps. If separate order is placed for these items, they are treated as spare parts and the pricing structure is different/higher.

This quote does not include any installation, concrete work, piping, valves, gauges or other fittings, control panels, or electrical except as described herein, or taxes of any kind.

Quotation is valid for 45 Days.

52

Terms of Payment - Net 30 Days

Purchase Orders should be made out to:

APSCO, Inc.
P.O. Box 2639
Kirkland WA. 98083
Ph (425) 822-3335 / Fax (425) 827-6171
Attn: Connie Murray
email: cmurray@apsco-inc.com

If you have any questions or we can be of further assistance, please let us know.

Randi, I will be on vacation the week of September 20 so be sure to send revised purchase order release to Connie with copy to me.

Thank you

Elaine Stone
APSCO, INC.
PH: (360) 735-8580 / Fax: (360) 735-8594
e-mail: estone@apsco-inc.com